

Decoraçõe

TORRI

"Places speak. You have to listen."

Mário Caeiro

#### **Forewords**

Torrão, a village in Portugal's Alentejo, where time whispers through its alleys. In the quietness, it remains hidden, embraced by age, slowly fading.

In January 2024, along with 20 architecture students from XJTLU, we embarked on a journey to unravel the beauty of this hidden gem. A town of mere whispers on the map, Torrão bewitched us with its ageless charm and eccentric inhabitants, guardians of traditions etched into the very soil they tread.

From the tranquil embrace of outdoor public spaces to the haunting beauty of derelict sites, each chapter of our research unveiled a new layer of the town's rich tapestry carefully documented by our team.

This booklet is more than just a collection of facts and figures; it is a testament to the timeless beauty of a place where history and heritage intertwine. May it serve as a humble tribute to the nostalgia that lingers in every corner of Torrão, and a reminder of the enduring beauty found in the quiet embrace of a quiet place.

### XJTLU × DaST

#### **Acknowledgement**

Xi'an Jiaotong Liverpool Univeristy

Project Supervisor: Jess Yu


Teaching Team: Jess Yu, Brett Gu

Students: Ao Liu, Beining Zhang, Chung Yin Matthew Yeung, Guangyao Cao, Haige Li, Hongxuan Zhu, Jiaxin Qian, Junli Chen, Kaiqing Tan, Lan Wei, Peiyao Xiao, Ruiyan Li, Ruofan Lin, Shengtong Liu, Yigao Liu, Yi Pan, Yi Zhang, Yilin Wang, Zike Qiang, Ziyi Huang.

Design a Sustainable Tomorrow

Project Team: Frederic Coustols, Maria Coustols, Mário Caeiro, Sammy Gao, Vasco Braga, Filipa de Assis, Sara Ibrahim, Angelica Rimoldi, local villagers of Torrão

Work Period: Jan 2024









Nomads Gro

"The Tagus is not more beautiful than the river that flows through my village Because the Tagus is not the river that flows through my village."

Fernando Pessoa, The River of My Village



# **Table of Content**

Chapter 1. Outdoor Public Space

Chapter 2. Civic Facilities

Chapter 3. Derelict Sites

Chapter 4. Scale of Space

Chapter 5. Materiality & Construction Techniques

Chapter 6. Key Architectural Features

Chapter 7. Windows and Doors

Chapter 8. Ornamentations

Chapter 9. Hardscape

Chapter 10. Landscape



# SMALL COMMUNAL RESTING AREA







# SMALL COMMUNAL RESTING AREA











# **SMALL COMMUNAL RESTING AREA**










# LARGE COMMUNAL RESTING AREA

Bernardim Ribeiro Square, Pç Bernardim Ribeiro 11



4 WHISPERS OF TORRÃO CHAPTER 1. OUTDOOR PUBLIC SPACE








Jardim dos Paus, Rua 2 de Abril

# LARGE COMMUNAL RESTING AREA

Parque Infantil do Torrão, Jardim do Torrão







# LARGE COMMUNAL RESTING AREA

Jardim da Fonte Santa, Rua da Fonte Santa













PARKING LOT

8 WHISPERS OF TORRÃO CHAPTER 1. OUTDOOR PUBLIC SPACE

#### **WATER POINT**



# PAVEMENT TEXTURE IN PUBLIC AREAS

















Most of the pavements in Torrão are constructed from gravel or regular stone pieces pieced together. Occasionally, different materials are employed to distinguish pedestrian paths from car lanes. Newly constructed pavements are mostly surfaced with tar.





10 WHISPERS OF TORRÃO CHAPTER 1. OUTDOOR PUBLIC SPACE











# **WIDE ROADS**

In areas with a high volume of traffic and high speeds, sidewalks should be considered for safety issue.













# **ALLEYWAYS**

The alleyways, which accommodate both cars and pedestrians, are rougher, resulting in lower speeds.

WHISPERS OF TORRÃO CHAPTER 1. OUTDOOR PUBLIC SPACE







## **FOOTPATH ONLY**

Some sections of the road are inaccessible to vehicles due to narrow access points, obstruction by outdoor extensions, or stairs. These areas only allow enough room for pedestrians and smaller vehicles to pass.

# DAMAGED ROADS

Many of the roads, located at the village boundaries, are badly damaged and in poor condition.









#### PARISH COUNCIL AND CITIZEN SPACE

The village of Torrão is located 35km from Alcácer do Sal, 45km from Évora and 87km from Setúbal and has 372,763 km2. The main accessibility is the EN2, which connects Montemor-o-Novo and Ferreira do Alentejo. The parish has 1.936 inhabitants.

Located on the right bank of the Xarrama river (a tributary of the Sado), between Alto Alentejo and Baixo Alentejo, it has a great historical past, being a town with roots in the Neolithic Period.






#### CREDIT AGRICULTURAL BANK

Crédit Agricole Groupe (CA) is a Portuguese national financial group composed of a number of local banks (Caixas Agrícolas) and specialized companies. Its central institution is the Caixa Central de Crédito Agrícola Mútuo.

18 WHISPERS OF TORRÃO CHAPTER 2. CIVIC BUILDINGS



#### **SOUVENIR SHOP**

In souvenir shop, you can expect to find things like locally made crafts, postcards, artwork, and other unique items that represent Torrão.



#### **BAR AND CAFE**

Bars and cafes are great places to relax, meet people, and enjoy local flavors. In a typical bar or cafe in Torrão, you might find a variety of wines, as well as local dishes.



#### **GROCERY STORE**

In Torrão, grocery stores offer a variety of local and international food products. Fresh fruits and vegetables, dairy products, meats, seafood, canned and dry goods, bread and pastries, beverages, and household items are generally available. Many stores also carry a selection of local cheeses, sausages, olives, and wines, giving you a chance to try local products.



#### LOCAL RESTAURANT

When visiting Torrão, you can expect local restaurants to offer a rich range of Portuguese dishes.



















#### **AUTO REPAIR SHOP**

Auto repair shops, also known as garages, provide services related to the maintenance and repair of motor vehicles. Services offered can range from routine preventive maintenance like oil changes and tire rotations, to troubleshooting and repair of mechanical problems.





#### PHARMACIE AND CLINIC

In the village of Torrão, there is only one pharmacy and one clinic. This shortage of medical facilities poses a significant challenge for an aging community, especially in emergencies. Villagers must travel to nearby cities or villages for more critical medical conditions.



#### **TAEKWONDO GYM**

A Taekwondo gym, also known as a dojang, is where students learn and practice Taekwondo, a Korean martial art. These facilities typically have an open, matted area for training, and may also have equipment like kicking bags, shields, and paddles for practice.

26 WHISPERS OF TORRÃO CHAPTER 2. CIVIC BUILDINGS 2



#### THE MAIN CHURCH

A tribute to Torrao's patron saint, Nossa Senhora da Assuncao, the Main Church was built in Castelos' upperarea, the oldest place in the village.



### **PRIMARY SCHOOL**

Primary schools cater to children between the ages of 6 and 10 in Portugal. They provide the foundational elements of a child's education, focusing on reading, writing, arithmetic, and an introduction to subjects like science, social studies, art, and physical education. It's also here where children in Portugal are first introduced to English as a second language.










# **WATER TOWER**

It is known that the name Torrao comes from theword Torrejam, which means Big Tower.

30 WHISPERS OF TORRÃO CHAPTER 2. CIVIC BUILDINGS





# DAMAGE LEVEL

- Level 1: Basic damage, with the basic components intact and repaired so that they can be used again.
- Level 2: Serious damage, infrastructures can no longer be used, but the overall structure is still preserved.
- **Level 3**: Total damage, most of the house objects are lost, only the foundation remains, mostly used as a historical monument, and will not be rebuilt.



Location:

R. Nossa Sra. da Albergaria 1, Torrão, Portugal

Damage level:

**Building function**: Hospital

**Size**: 12×9m

Storey:2

Infrastructure: Masonry







# **BASIC CONDITION**

Only two walls remain, most of which have been lost. A brick structure resembling an arched door remains on the site. It used to be a local hospital, but now it's abandoned.

Location:

R. Poço do Mau 13, Torrão, Portugal

**Building function:** Monasteries/


churches

Storey:2-3

Damage level:

Chronology: Sixteenth-19th centuries

Infrastructure: Masonry and stone









# **HISTORY**

It is a convent of poor clares that combines an unexpected monumentality in the context of the village of Torrão with the great stripping and decorative austerity of its facades.

It retains echoes of the Renaissance repertoire in the church's portal, and some baroque "updating" well expressed in the mural paintings that should be restored, as well as the entire complex, of which the cloister, fence, well and nora are also preserved.





Location:

R. Sebastião Brites Pinto, Torrão, Portugal

**Building function:** Family House

Damage level:

**Size:** 12×9m

Storey:1

Infrastructure: Masonry



# **BASIC CONDITION**

It was largely destroyed and converted into a vegetable plot for the neighbouring residence.



Location:

R. Penedo Minhoto 12, Torrão, Portugal

**Building function:** Family house (on

sale)

Damage level:

Size: 9.9×12m

Storey:2

Infrastructure: Masonry







# **BASIC CONDITION**

The building appears to be under construction but is actually abandoned. There is only cement on the outside of the brick, no envelope.



Location:

R. Penedo Minhoto 4, Torrão, Portugal

**Building function:** Family House

Damage level:

**Size:** 11.2×9m

Storey:1

Infrastructure: Masonry



# **BASIC CONDITION**

The overall structure remains intact, with slight damage to the roof.



Location:

R. dos Lavradores 82, Torrão, Portugal

**Building function:** Olive oil factory

Damage level:

Size: 10.6×7m

Storey:1

Infrastructure: Masonry







#### **HISTORY**

Once a relatively important production plant providing jobs for the people of the village, it has been abandoned since 2000.



Location: R. da Fonte Santa 2, Torrão, Portugal

**Building function:** Grave Memorial

Damage level:

Storey:1

Chronology: 1st/5th centuries A.D



#### **HISTORY**

In the nineteenth century it was identified by Leite de Vasconcelos in the place called Fonte Santa "... a small Roman building, made of opus signinum, and which was perhaps a deposit of agago; around, many fragments of tegulas..."







Location:

R. de Beja 128, Torrão, Portugall

**Building function**: Family house

Damage level:

Storey:2

Infrastructure: Timber









# **BASIC CONDITION**

The building is located on the N2 road and is often passed by large lorries. There is a broken windmill standing in the yard.



Location:

Tv. do Cónego, Torrão, Portugal

**Building function:** Family house

Damage level:

**Size:** 28×14m

Storey:2

Infrastructure:

Masonry and stone



# **BASIC CONDITION**

Formerly used as a family home, the interior of the house is generally structurally intact, the exterior fencing is more visibly in disrepair



Location:

R. do Cónego 28, Torrão, Portugal

**Building function:** Family house

Damage level:

Size: 9×12m

Storey:2

Infrastructure:

Masonry







# **BASIC CONDITION**

The facade of the house has a distinctive peeling blue paint. Window frames on the second floor disappeared.





Location: R. do Cónego 11, Torrão, Portugal

**Building function**: Family house

Damage level:

**Size**: 12×12m

Storey:1-2

Infrastructure: Masonry









# **BASIC CONDITION**

The house retains its full facade and roof, with slightly detached walls. The glass on the second floor was damaged, and the interior of the house became a home for pigeons.

Location:

R. Cardins 19, Torrão, Portugal

**Building function:** Family house

Damage level:

Size: 21.5×6m

Storey:2


Infrastructure:

Masonry









# **BASIC CONDITION**

Parts of the exterior walls remain, and the interior is completely abandoned. The yard has become a home for stray cats

Location:

R. Marquês de Pombal 10, Torrão, Portugal

**Building function**: family residence

Damage level:

**Size:** 8 × 9.8m

Storey:1

Infrastructure: Masonry







#### **BASIC CONDITION**

The abandoned building retains only part of the perimeter wall and the roof structure, with the main gate and the left side facing wall almost completely damaged.





### Location

R. do Relógio 22, Torrão, Portugal

**Building function**: family house (on sale)

Damage level:

**Size:** 8× 9.8m

Storey: 1

Infrastructure: Masonry









### **BASIC CONDITION**

The abandoned house has severely damaged roof beams, while the wall structure as well as the gate and other components are basically intact.

### **15. FAMILY HOUSE**

Location:

R. do Relógio 46, Torrão, Portugal

**Building function**: family house

Damage level:

Size: 8 × 6m

Storey:1

Infrastructure:

Masonry









### **BASIC CONDITION**

The exterior paint on the walls and doors of this derelict building are partially broken, as well as the chimney is damaged. The roof tiles are largely intact





Location:

R. do Relógio 39 Torrão, Portugal

**Building function**: family house (on sale)

Damage level:

**Size:** 7.2 × 9m

Storey:1

Infrastructure: Masonry









### **BASIC CONDITION**

The roof beams are badly damaged, but the wall structure and components such as the gate are basically intact.

17.

Location:


R. da Estalagem 31 Torrão, Portugal

**Building function**: Factory

Damage level:

Storey:1

Infrastructure: Masonry











### **BASIC CONDITION**

All that remains of the building is a few broken walls and abandoned iron gates. It is at the entrance of the village.

18.

Location:

R.dos Pescadores, Torrão, Portugal

**Building function**: Olive oil factory

Damage level:

Storey:1

Infrastructure: Masonry











### **BASIC CONDITION**

The building had cracked walls, broken windows and a pile of construction waste inside. It used to be an olive oil factory, but it is no longer used.





Location:

R. Catarina Eufémia 40, Torrão, Portugal

**Building function**: family house

Damage level:

Storey:1

Infrastructure: Masonry







### **BASIC CONDITION**

71

The building's exterior protected construction was damaged, exposing the bricks inside. The roof tiles were also badly damaged.

20.

Location:

R. da Matriz 34, Torrão, Portugal

**Building function**: Family house (on sale)

Damage level: ■□□

**Size:** 7.2 × 9m

Storey:2

Infrastructure: Masonry









### **BASIC CONDITION**

The building had a striking chimney, a slightly chipped wall, and broken window frames. The blue paint was faintly visible.





Location: R. do Adro 15, Torrão, Portugal

**Building function**: Family house (on sale)

Damage level:

**Size:** 4.5× 9M

Storey:1

Infrastructure: Masonry







### **BASIC CONDITION**


Chimneys and window and door elements are preserved, but the roof is more severely damaged.




### **SCALE OF SPACE**

Torrao has a rich variety of architectural blocks, public parks, and other spatial typological types, and the changes in scale within the space provide people with different senses and experiences.

The following content provides readers with some intuitive comparisons between people and different spatial scales by recording different types of spatial scales.











Residential Houses



Junctions/Crosses



Vacant Land



**Green Patches** 



Plaza

### **TYPOLOGY**

Different types of functional spaces often bring different scales to people. In Torrao, there are several common types of spaces, from residential areas to open spaces to public parks, etc. The following will analyze the relationship between images and data.




3.5

# **PUBLIC BUILDINGS**

The filming location is located on a fork in the road opposite the grocery store, which is relatively wide and has a downhill tendency. The houses on both sides are relatively low, and the view is relatively broad

# RESIDENTIAL HOUSE

The street here is narrow and the buildings are relatively high. The street can only barely accommodate one person and one vehicle, which can give people a feeling of being blocked and crowded





### JUNCTIONS/CROSSES

This was documented at the intersection of three streets, right in front of the agricultural bank.



### STREETS

Streets of Torrao is covered with stone paving in different colors. This is filmed at another intersection of three streets










### **VACANT LAND**

Most of the open spaces in the village are small parking lots, with an average area of about 300 square meters, and the surrounding environment is relatively open, surrounded by some houses and green spaces



Some wider intersections may have public areas such as garbage stations and rammed earth platforms set up








# VEGETATION GREENLAND

These green spaces cover an area of approximately 50-200 square meters and are mostly private areas

### **GREEN PATCHES**

While the village boasts large areas of green space and parks, the majority are privately owned and not accessible to the public. These areas feature orange trees, oak trees, and even house a certain amount of poultry.





### **PLAZA**

The squares and public areas are places where the elderly in the village love to engage in activities at night, and they often enjoy gathering and chatting in these squares.

### **PUBLIC PARK**

The area of the square is around 150-300 square meters, depending on the different locations of the village







### **BRICK-STONE STRUCTURE**


Torrão is a village characterized by rustic building styles, often dominated by ancient Christian and Catholic churches featuring stone structures and a historical aesthetic.

In Portuguese architecture, the arch structure typically employs bricks as the primary material. These arches are frequently utilized to support the roof or ceiling, creating open spaces or providing structural support.























AQUI - CONVENTO DA TERRA








## WOOD STRUCTURE





### **BRICK-CONCRETE STRUCTURE**







### **BRICK-CONCRETE STRUCTURE**

The exterior wall of the house is mainly divided into four parts, from the inside out are: stone brick, rammed earth paint, plaster and various colors of paint.









### **COLOR COATING**

Traditional Houses in Torrão:

Buildings in rural areas are often simple and functional, reflecting traditional Portuguese architectural styles.

The houses are usually constructed of stone, tiles and wood, sometimes with brightly colored walls to add visual appeal. These colored exterior paints are chosen by the residents according to their own preferences, and neighboring houses usually do not use the same color.



### **NEW BRICK**

The reconstruction of houses in Torrão generally preserves only the foundations, and today the main material used for the structure of the houses is hollow bricks, which have the advantage of being lighter in weight, better insulated, more acoustic, and less material.

### **ORIGINAL BRICK**

The main material used in the construction of the earliest houses was **solid brick**, which has been preserved to this day due to its resistance to weathering.







### WALL COATING

When it comes to exterior paints, Torrão houses are likely to use highly weather resistant paints that not only have long-lasting colors, but are also able to withstand harsh weather conditions, ensuring that the exterior of the house remains aesthetically pleasing for a long period of time. There is also a trend towards environmentally friendly paints, which are harmless and friendly to the health of the occupants.























CHAPTER 6. KEY ARCHITECTURAL FEATURES

#### **ROOF SYSTEM: TILE TYPE**

The roof tiles of Torrão are an important element of Portuguese architecture, adding a unique charm to this beautiful and tranquil town.

The roofs here typically feature traditional ceramic tiles, showcasing a strong Mediterranean style.





TYPE 1



118 WHISPERS OF TORRÃO CHAPTER 6. KEY ARCHITECTURAL FEATURES 11



120





**TYPE 3** 



### **ROOF SYSTEM: STRUCTURE**

The earliest roof structures were mostly made of wood and did not have insulation layers. Due to the poverty and limited resources of people in the past, building material and techniques were quite constrained






The early roofs were thatched with reeds on wooden beams to support the tiles. There was no cement between the tiles, making them relatively fragile with poor stability. According to local residents, the first house in Torrão did not have windows, likely due to the intense heat in summer and the cold in winter. The ventilation for the entire house was achieved through gaps between the roof tiles.



22 WHISPERS OF TORRÃO CHAPTER 6. KEY ARCHITECTURAL FEATURES 1:









This construction method does not rely on cement for reinforcement, and the structural design of each tile can enhance stability.







### **ROOF SYSTEM: SKYLIGHT**

Due to the extremely hot summers, many houses in the southern part did not have windows. Even if there were windows, certain devices were installed.

As a result, the internal lighting of the houses was restricted. Therefore, local residents chose to get light from the roof.

Some roofs had skylights, while others used glass or plastic instead of tiles to allow more light to enter.

### **ROOF SYSTEM: CHIMNEY**

Almost every household has a chimney.


In addition to expelling kitchen fumes, it is more often used to release smoke after heating with a fireplace.

Moreover, the residents of Torrão enjoy making sausages, and they usually hang the sausages inside the chimney pipes for smoking.



Chimney like this are relatively modern in form, typically featuring an elegant appearance.





#### WINDOWS AND DOORS

Torrão is a civil parish and town, in the municipality of Alcácer do Sal, in the Portuguese district of Setúbal, bordering on the districts of Évora and the Beja.

Torrao, although it exists as one of the poorer villages in Portugal, refurbishes the facades of houses throughout the town every year. Each house has its own individual facade, with many different types of doors and windows.





#### **DOORS OF PUBLIC FACILITIES**

Location: Tv.do Conego

Function: Separate the courtyard from the public space Appendix: Inside is an abandoned garden. The gates are made of iron and are double doors. The doors have iron handles.





Location: R. Dr. Bento de Jesus Caraca Road

Function: Separate the courtyard from the public space
Appendix: The two sides of the door are shaped stone columns, the lower part is 2/3 iron door plate, the upper part of the remaining 1/3 is iron frame, the whole door is opened or fixed through the internal latch.



#### WINDOWS AND DOORS OF PUBLIC FACILITIES

Location: Bibilioteca Maria Rosa Colaco

Function: Separate the interior rooms and public Spaces

Appendix: The only library in the town of Torrao. The material used for the door is steel. The entrance has a low threshold and opens as a pair of doors. The door and the window on the left side have light-permeable windows made of wire mesh to increase the communication between the inner and outer space.





Location: R. Dr. Bento de Jesus Caraca Road

Function: Separate the courtyard from the public space. Appendix: Fire garage doors are twice as high as the average

residential garage door. It is a vertical windproof automatic sliding door with aluminum alloy and stainless steel door frame.

#### **POST OFFICE**

Location: R. 5 de Outubro Road

Function: Separate the interior rooms and public Spaces.

Appendix: It has the same blue frame paint as the doors, but with marble steps instead of stone.







Location: R. de Beja

Function: Separate the interior rooms and public Spaces. Appendix: Compared with other Windows, the window has more shutters to block the glare of the sun. More spiral plastic curtain outside the door, heat insulation and wind. The door also has an extended eaves.






#### **PUBLIC FACILITIES**

Location: Church of Nossa Senhora da Assuncao

Function: Separate the interior rooms and public Spaces.

Appendix: The church has double doors with stylised carvings and

is made of wood.





#### **PUBLIC FACILITIES**

Position: Taberna Ventura

Function: Separate the interior rooms and public Spaces. Appendix: a cafe close to the village where the residents meet to play cards. The door is made of aluminium and opens and closes with a counter-opening. The entrance is curtained. There is a small glass window on the door, which allows the sale of goods through the door without opening the door, providing a certain degree of security.





#### **PUBLIC MEDICAL CENTER**

Location: R. 5 de Outubro Road

**Function:** Separate the interior rooms and public Spaces. **Door:** Stone arched door frame embedded with glass door, glass door foreign affairs wire anti-theft net.

Windows: The Windows have the same stone frame as ours, and are notable for the stone drain below.



#### **PUBLIC FACILITIES**

**Location:** Pc Bernardim Riberiro 9 (close to the visitor centre square of the town of Torrao)

Function: Separate the interior rooms and public Spaces.


Windows: As the interior is not inhabited, the inhabitants have walled off the original windows to prevent birds from entering the interior to make their nests, and each window has a terrace with iron railings.

**Doors:** The doors are made of aluminium alloy. Also on the doors are small windows for communication between the interior and exterior.



# WINDOWS AND DOORS OF RESIDENTIAL PROPERTY

In this research, residential homes serve as the largest percentage of housing types in the town as a whole. The highest percentage of our research on windows and doors is also on the windows and doors that appear in the lives of the residents.















#### **RESIDENTIAL PROPERTY**


Location: R. de Beja 101

**Doors:** Double shutters maximise the ventilation and cooling of the interior of the house by helping residents in different situations in summer and winter.

The windows on the door also preserve the security of indoor-outdoor communication to some extent.

Windows:This combination of doublelayered blinds windows with a single door is one of the most common in the town of Torrao due to its convenience.





#### **RESIDENTIAL PROPERTY**

Position: 79 R. do Conego

**Appendix:** This combination of sliding windows and single-opening doors with small windows is another residential window and door option that has taken the town of Torrao by storm. These windows are made of aluminium with small internal solid wood windows that open and close. The ability to freely choose whether or not to open to the outsid.



#### **GRAFFITI DOOR**

**Location:** R. Sacadura Cabral

Function: Separate
the courtyard from the
public space.
Appendix: In many
warehouse doors, rare
iron doors with graffiti,
with characteristic
lasting appeal, give a
person a bright at the
moment.

# BUILT-IN DOORS IN RESIDENTIAL AREAS

Location: R. da Liberdade

Appendix: There is usually a small under-gallery space between the door and the road, separated by an iron fenced gate.

**Decoration:** The door will have striped or patterned grids for decoration and anti-theft.

















### **DOOES WITH TILES BESIDE**

Location: R. 5 de Outubro

Function: Separate the interior rooms and public Spaces.

**Appendix:** Usually people with tiled doors and Windows are richer, and the decorative iron grating on the door, including the doorknob, will be more exquisite and the color match will be richer. The door will have a small square hole for newspapers and letters.

#### **DOORS WITH BALCONY**

Location: R. Cardins

Appendix: The Windows with balconies are generally more delicate, and the exterior frame of the door or window has decorative elements. The fence of the balcony is usually a grid with iron pattern, but the balcony space is usually small and can only be a lookout, with no other function.



# SOME NOTEWORTHY FEATURES

During our study, we delved into various aspects related to doors and windows, uncovering fascinating insights that deserve our attention and consideration. One of the key areas we explored was the function of these architectural elements.

Furthermore, we analyzed the structure of doors and windows, recognizing their crucial role in maintaining the integrity of a building's design.









# VARIOUS SMALL WINDOWS

**Location:** Residential areas and public service areas

Shape: Basically round or

rectangular

Frame: The inlaid Windows in the residential area are mostly painted around them. The public service area has less window paint but marble sill.

Glass: The inlaid Windows in the residential area are largely surrounded by clear glass. The Windows in the public service area are translucent patterned glass.





150 WHISPERS OF TORRÃO CHAPTER 7. WINDOWS AND DOORS 15





#### **IRON GATE**

Location: Tv. Dona Inacia

Material: The door of carbon steel plate is cheap, but easy to rust, catalpol plate can effectively prevent rust, and color coating can not only enrich the surface color, but also enhance the ability of rust prevention.

Handle: The special shape of the door ring is a major feature, usually the door and the door ring connected with the part of the decorative pattern.

#### **DOORS WITH DOUBLE LAYERS**

Location: R. do Relogio

Structure: One type is the outer iron door or glass window to protect the inner wooden door, wooden window, ventilation or light can be provided without opening the door.

Another type is an iron door with a glass window inside. In the case of strong sunlight, a curtain will be added to block the light.















Location: Tv. de Santana

**Size:** Large (2.4×1.8m), medium (2.4×1.1m), small (1.8×0.8m)

**Appendix:** Mostly large-size doors are public facilities or doors that require vehicles to enter, medium-size doors are small commercial Spaces or residents, and small-size doors are mostly residents.











#### MATERIALS USED IN DOORS AND WINDOWS

Location: Residential areas and public service areas

Cloth curtain: Cloth curtain can block light, adjust indoor temperature, prevent indoor items from aging by the sun. Iron patterned grid: Used for protection and decoration. Frosted glass: The function is similar to curtains, and the common grain is bubble ripple and water ripple frosted glass. Plastic louvers: The function is similar to curtains, most of them are external.

**Marble countertops:** The use of marble can make the window sill position seam less.









#### **CERAMIC WALL TILE**

Mainly decorative tiles made by wealthy families in the past covered the walls in order to protect the house from being damaged At present, new residents rarely adopt this form, just for the convenience of scrubbing and placing these tiles in the kitchen and bathroom.



Rua Dr.

JOSE























#### PRAYER TILE PAINTING

In order to bring good luck to their homes, families would put up tile paintings with images of gods, mostly Jesus and the Virgin Mary, on their doorways, and this phenomenon mostly occurred in rural areas.







#### PRAYER TILE PAINTING

The other is more specific, more concrete wishes such as praying for a good harvest.



#### **RECORDING TILE PAINTING**

The historical story of the sculpture is mainly recorded next to the monumental sculpture. Government funds are mainly invested in central cities such as Lisbon, while it is difficult for poor areas such as Torrao to have funds to protect such historic monuments. At this stage, ceramic tile painting is mainly used to explore the

historical appearance of this commemorative sculpture.

















**RELIEFS** 

162 WHISPERS OF TORRÃO CHAPTER 8. ORNAMENTATIONS 16

















PILASTER SCULPTURE



















HANDRAILS OTHERS

# MONASTIC DECORATION















**CHAPTER 8. ORNAMENTATIONS** 



#### **SIGNAGE**

#### Guideboard

These street signs are mostly placed on the side of the road and near the house to alert traffic and pedestrians.





























### SIGNAGE

# **Street Nameplate**

Showing the direction and distance of the destination.

# SIGNAGE

To Guide Visitors Through The Village



- Vehicle can go through
- Turn Left



- Vehicle can go through
- Crossroad



- Vehicle can go through
- Go straight















DRAINAGE

























Historic Fountain

# **FOUNTAIN**

# Story behind historic fountain:

These street signs are mostly placed on the side of the road and near the house to alert traffic and pedestrians.




Historic Fountain

**CHAPTER 9. HARDSCAPE** 

**PAVING** 

Different Types Of Pavement

# **URBAN FURNITURE**



In the Yard



Outdoor Sink And Dining Area



Conch shells under trees



Dog Shack



# **FLORA**


UNCOUNTABLE NOUN [with singular or plural verb]


You can refer to plants as flora, especially the plants growing in a particular area.


[formal]

...the variety of food crops and flora which now exists in Torrao.

Synonyms: plants, vegetation







# **JARDIM**

English: Garden

Word forms: plural, 3rd person singular present tense gardens, present participle gardening, past tense, past participle gardened Gardens are places like a park that have areas of plants, trees, and grass, and that people can visit and walk around.





This garden is located beside one of our sites, in front of an old olive oil production factory,. The garden has a variety of small trees, such as lemon trees and orange trees. Surrounding the trees are various flowers like the Treasure Flower and Gazanias







Sour Orange

Treasure Flower

Lemon









White Trailing Daisy

Magic Tower

### **JARDIM DE S. FRANCISCO**

The largest garden in the area, located beside the convent, houses a coffee shop and a children playground, making it the most often frequented garden in Torrao.









**Grey Santolina** 

Kikuyu Grass

Persian-lilac

### **JARDIM DOS PAUS**

Located in the south east corner of the town, the Jardim dos Paus is nearby a couple of public facilities, such as a public swimming pool and a roman bath. There is a primary school on the hill beside so children's laughter can be heard while walking in the park





This garden is located in from of our studio, everyday when we arrive at the studio early in the morning, we can see the trees swaying in the morning dew. Everynight, they wait patiently for us to leave and greet us in the morning. With faith, I believe that after we leave Torrao they will greet the next batch of visitors with the same patience.







Fountain not in use

Statue

Red Bottlebrush









Log beside lake

#### WATER RESERVIOR

The water reservoir situates in the south west portion of town. At low tide, we stepped on the wet mud, witnessing the fallen bark on the ground, stones stacked on the shore. The sky and clouds melt into one with the glassy lake, with the chimes on the lambs being the only voice in this serene place.

"The Tagus has enormous ships,
And for those who see in everything that which isn't there,
Its waters are still sailed,
By the memory of the carracks.

...

The river of my village doesn't make one think of anything.
Whoever is next to it is simply next to it."

Fernando Pessoa, The River of My Village